

Did you know? Mini-Vac Units

By utilizing Ecoserv's Mini-Vac System you could be saving thousands of dollars.

Our customers with jobs requiring the cleaning of sump tanks, heater treaters, water process vessels, or any other applications where large solid particulates may be encountered are presently saving thousands of dol-lars with the Mini-Vac System. Join them today!

Case Study

Customer Challenge

375 bbls of product needed to be removed from a 400 bbl sump tank. The sump contained concrete, drilling mud, sand, trash, and other debris that causes continual diaphragm pump failures or malfunctions and clog hoses.

Assessment

Diaphragm Pumps vs Mini-Vac

Diaphragm Pump Setup

- Carry 5 gallon buckets of product up elevators and stairs into cutting boxes
- Breakdown & rebuild diaphragm pumps to remove trash & debris
- More cutting boxes required to complete the job due to the added wash water needed to break up and move product
- Additional diaphragm pumps required which increase costs

Mini-Vac Setup

- No manual movement of product
- Large particulates can easily be vacuumed into cutting boxes without stoppages
- Fewer cutting boxes required
- Little to no wash water needed to move product

14 hours per day

Diaphragm Pump Package w/ Crew						
Equipment & Personnel	Cost	Days on Job	Total Cost			
Additional Dia. Pumps (3)	\$285	9	\$2,565			
Toolhouse Package	\$985	9	\$8,865			
Air Compressor	\$135	9	\$1,215			
Breathing Air Package	\$285	9	\$2,565			
Superintendent	\$45/hr	9	\$5,670			
Cleaning Techs (8)	\$140/hr	9	\$35,280			
Cutting Boxes (50)	\$1,475	9	\$13,275			
Disposal	\$15.75/bbl		\$11,812.50			

Mini-Vac Package w/ Crew						
Equipment & Personnel	Cost	Days on Job	Total Cost			
Mini-Vac Package	\$450	4	\$1,800			
Toolhouse Package	\$985	4	\$3,940			
Air Compressor	\$135	4	\$540			
Breathing Air Package	\$285	4	\$1,140			
Superintendent	\$45/hr	4	\$2,520			
Cleaning Techs (8)	\$140/hr	4	\$15,680			
Cutting Boxes (25)	\$737.50	4	\$2950			
Disposal	\$15.75/bbl		\$5906.25			

Total cost of standard package = \$81,247.50

Total cost of Mini-Vac package = \$34,476.25

Result

- Over 50% reduction in job time
- \$46,768.25 in savings
- 97% Reduction in waste water
- 50% Fewer cutting boxes needed
- 0% downtime due to equipment malfunction
- Enhanced safety (no manual movement of product)

Mini-Vac Specifications						
Dimensions	Weight	CFM	Power	Inches of Hg		
5' 5" L x 5' 5" W x 7' H	2,400	500	Diesel	27		

